

Bathroom - 2 Cae Glass, Penrhwiwr, Tonypandy.					Survey Type >		Refurbishment		Initial Survey Date(s) >							07/02/2017						
2220AS1100A					Register Type >		Final		Risk ratings							Management Action						
Report Section	Extrapolated from Site Ref	UPRN (if applicable)	Lab Ref	Site Ref	Area or room	Position	Component description	Material	Asbestos ID	Extent / approx quantity	** Accessibility	** Damage	** Surface treatment	Asbestos type (1 = Chrysotile, 2 = Amosite, 3 = Crocidolite)	Total Material Risk rating "A"	Total Priority Risk rating "B" - Score breakdown available on request	Total Risk Rating "A+B"	 Recommendation	Last date ACM inspected	Last date ACM modified	Note	Licensed work?
G			NGAR03523-2	2220AS1100A-002	Bathroom	Ceiling	'Artex' - 'Random'	Textured coatings & joint compound	Negative asbestos sample	6SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	07/02/17		Previously sampled as negative please see 2220AS1100-002	
G			PHH1214-1	2220AS1100A-004	Bathroom	Under all flooring layers	Green henison backed vinyl sheet flooring	PVC vinyl floor tiles & unbacked PVC flooring	Negative asbestos sample	4SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	07/02/17			
H				2220AS1100A-001	Bathroom	Floor and under current flooring	Wood effect vinyl tiles	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	8SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	07/02/17		2 Layers of self adhesive tiles	
H				2220AS1100A-003	Bathroom	Walls around bath	Ceramic tiles	Other	Discounted material (not sampled)	2SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	07/02/17		Ceramic	

* risk assessment required prior to work.

Where 'Carry Out Repairs', 'Seal', 'Encapsulate' or 'Enclose' is recommended, it is implicit that the ACM is also classified as 'Record, Manage and Monitor'.