

67 Corbett Street, Treherbert, Treorchy.				Survey Type >			Part Management and Part Refurbishment			Initial Survey Date(s) >						04/02/2022							
2220AS1397				Register Type >			Final			Risk ratings						Management Action							
Report Section	Extrapolated from Site Ref	UPRN (if applicable)	Lab Ref	Site Ref	Area or room	Position	Component description	Material	Asbestos ID	Extent / approx quantity	** Accessibility	** Damage	** Surface treatment	Asbestos type (1 = Chrysotile, 2 = Amosite, 3 = Crocidolite)	Total Material Risk rating "A"	Total Priority Risk rating "B" - Score breakdown available on request	Total Risk Rating "A+B"	 Recommendation		Last date ACM inspected	Last date ACM modified	Note	Licensed work?
G			PHH26 076-1	2220AS13 97-001	Ground floor - All areas	Under current floorings	Cream tiles and adhesive	PVC vinyl flooring and adhesive	Negative asbestos sample	40SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
G			PHH26 076-2	2220AS13 97-002	Ground floor - Kitchen	Under sink	Bitumen pad	Bitumen coatings on metal	Negative asbestos sample	Small Quants	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
G			PHH26 076-3	2220AS13 97-005	Ground floor - All areas except lounge	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	20SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
G			PHH26 076-4	2220AS13 97-006	Ground floor - Lounge	Ceiling	'Artex' - 'Fan'	Textured coatings & joint compound	Negative asbestos sample	10SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
G			PHH26 076-5	2220AS13 97-007	First floor - All areas	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	30SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
G			PHH26 076-6	2220AS13 97-010	Porch	Edge of porch roof	Lining board	Insulating board	Negative asbestos sample	1LM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
H				2220AS13 97-003	Ground floor - Kitchen	Within boiler	Gaskets	Textiles - Gaskets & washers	Discounted material (not sampled)	Small Quants	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
H				2220AS13 97-004	Ground floor - Kitchen	Floor	Cream sheet vinyl	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	8SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
H				2220AS13 97-008	Roof space	Under roof	Sarking felt	Bitumen roofing felts	Discounted material (not sampled)	40SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				
H				2220AS13 97-009	First floor - Bathroom	Behind toilet	Waste pipe	Reinforced plastic and resin composites	Discounted material (not sampled)	Small Quants	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	04/02/22				

* risk assessment required prior to work.

Where 'Carry Out Repairs', 'Seal', 'Encapsulate' or 'Enclose' is recommended, it is implicit that the ACM is also classified as 'Record, Manage and Monitor'.