

49 Blaencwm Terrace, Treochy.						Survey Type >		Type 2		Initial Survey Date(s) >						14/12/2009					
2220AS2						Position	Component description	Material	Asbestos ID	Extent / approx quantity	Accessibility	Damage	Surface treatment	Risk ratings			Management Action				
Report Section	Extrapolated from Site Ref	UPRN	Lab Ref	Site Ref	Area or room									Total Material Risk rating "A"	Total Priority Risk rating "B"	Total Risk Rating "A+B"	 Recommendation				Last date ACM inspected
G		03BLC0 4900	91558/ B457-1	2220AS2-001	Ground floor - Kitchen	Under side sink top	Bitumen pad	Bitumen coatings on metal	Negative asbestos sample	1No	NA	NA	NA	NA	NA	NA	No action not an ACM	14/12/09			
G		03BLC0 4900	91558/ B457-2	2220AS2-003	Ground floor - Lounge and hall	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	16SM	NA	NA	NA	NA	NA	NA	No action not an ACM	14/12/09			
G		03BLC0 4900	91558/ B457-3	2220AS2-004	First floor - Bedrooms 1, 2, bathroom and landing	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	34SM	NA	NA	NA	NA	NA	NA	No action not an ACM	14/12/09			
G		03BLC0 4900	91558/ B457-4	2220AS2-005	Roof space	Under side roof coverings	Sarking felt	Bitumen roofing felts	Negative asbestos sample	50SM	NA	NA	NA	NA	NA	NA	No action not an ACM	14/12/09			
H		03BLC0 4900		2220AS2-002	Ground floor - Kitchen	Floor	Grey vinyl sheet flooring	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	12SM	NA	NA	NA	NA	NA	NA	No action not an ACM	14/12/09			
H		03BLC0 4900		2220AS2-006	First floor - Bathroom	Floor	Blue vinyl sheet flooring	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	4SM	NA	NA	NA	NA	NA	NA	No action not an ACM	14/12/09			