

| 1 Graig Wen, Maerdy. | | | | | Survey Type > | | | Management | | Initial Survey Date(s) > | | | | | | 17/01/2011 | | | | | |
|----------------------|----------------------------|----------------------|------------|----------------|---------------------------------|---------------------------------|------------------------------|--|-----------------------------------|--------------------------|------------------|-----------|----------------------|--------------------------------|--------------------------------|-------------------------|---|----------|--|--|-------------------------|
| 2220AS246 | | | | | | | | | | | | | | | | | | | | | |
| Report Section | Extrapolated from Site Ref | UPRN (if applicable) | Lab Ref | Site Ref | Area or room | Position | Component description | Material | Asbestos ID | Extent / approx quantity | ** Accessibility | ** Damage | ** Surface treatment | Risk ratings | | | Management Action | | | | |
| | | | | | | | | | | | | | | Total Material Risk rating "A" | Total Priority Risk rating "B" | Total Risk Rating "A+B" |  Recommendation | | | | Last date ACM inspected |
| A | | | NGA30 49-5 | 2220AS24 6-010 | External - Roof to porch | Undercloak to verge | Lining boards | Cement - Fully comp flat sheet, tiles, slates & boards | Positive asbestos sample | 2LM | 0 | 0 | 0 | 4 | 1 | 5 | Record, manage & monitor | 17/01/24 | | | No* |
| G | | | NGA30 49-1 | 2220AS24 6-002 | GF - Kitchen | Under side sink top and drainer | Bitumen pads | Bitumen coatings on metal | Negative asbestos sample | 2No | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| G | | | NGA30 49-2 | 2220AS24 6-003 | GF - All rooms | Ceilings | 'Artex' - 'Stipple' | Textured coatings & joint compound | Negative asbestos sample | 35SM | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| G | | | NGA30 49-3 | 2220AS24 6-006 | GF - Hall, stairs, FF - Landing | Top half of walls | 'Artex' - 'Comb' | Textured coatings & joint compound | Negative asbestos sample | 24SM | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| G | | | NGA30 49-4 | 2220AS24 6-008 | FF - All rooms | Ceilings | 'Artex' - 'Stipple' | Textured coatings & joint compound | Negative asbestos sample | 35SM | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| H | | | | 2220AS24 6-004 | GF - Toilet | Floor | Grey vinyl sheet flooring | PVC vinyl floor tiles & unbacked PVC flooring | Discounted material (not sampled) | 2SM | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| H | | | | 2220AS24 6-005 | GF - Kitchen | Floor | Black vinyl sheet flooring | PVC vinyl floor tiles & unbacked PVC flooring | Discounted material (not sampled) | 4SM | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| H | | | | 2220AS24 6-007 | FF - Bathroom | Floor | Blue vinyl sheet flooring | PVC vinyl floor tiles & unbacked PVC flooring | Discounted material (not sampled) | 2SM | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| H | | | | 2220AS24 6-009 | Roof space | Under roof coverings | Sarking felt | Bitumen roofing felts | Discounted material (not sampled) | 40SM | NA | NA | NA | NA | NA | NA | No action not an ACM | 17/01/11 | | | |
| I | | | | 2220AS24 6-001 | GF - Lounge | Within wall mounted back boiler | Internal gaskets and washers | Textiles - Gaskets & washers | Removed | Small Quants | NA | NA | NA | NA | NA | NA | No action not an ACM | 21/04/16 | | Gas fire has now been removed prior to re-visit 21/04/2016 | |

* risk assessment required prior to work.

Where 'Carry Out Repairs', 'Seal', 'Encapsulate' or 'Enclose' is recommended, it is implicit that the ACM is also classified as 'Record, Manage and Monitor'.