

2 Summerfield Court, Trealaw, Tonypanydy.					Survey Type >			Management		Initial Survey Date(s) >						31/03/2011					
2220AS461																					
Report Section	Extrapolated from Site Ref	UPRN (if applicable)	Lab Ref	Site Ref	Area or room	Position	Component description	Material	Asbestos ID	Extent / approx quantity	** Accessibility	** Damage	** Surface treatment	Risk ratings			Management Action				
														Total Material Risk rating "A"	Total Priority Risk rating "B"	Total Risk Rating "A+B"	 Recommendation				Last date ACM inspected
G			NGA40 44-1	2220AS46 1-002	GF - Hall, toilet and kitchen	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	23SM	NA	NA	NA	NA	NA	NA	No action not an ACM	31/03/11			
G			NGA40 44-2	2220AS46 1-003	GF - Lounge	Ceiling	'Artex' - 'Fan'	Textured coatings & joint compound	Negative asbestos sample	15SM	NA	NA	NA	NA	NA	NA	No action not an ACM	31/03/11			
G			NGA40 44-3	2220AS46 1-005	FF - All areas	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	40SM	NA	NA	NA	NA	NA	NA	No action not an ACM	31/03/11			
G			NGA40 44-4	2220AS46 1-007	External - Porch canopy	Undercloak	Lining board	Insulating board	Negative asbestos sample	1LM	NA	NA	NA	NA	NA	NA	No action not an ACM	31/03/11			
H				2220AS46 1-001	GF - Kitchen	Underside sink top	Bitumen pad	Bitumen coatings on metal	Discounted material (not sampled)	1No	NA	NA	NA	NA	NA	NA	No action not an ACM	31/03/11			
H				2220AS46 1-004	GF - Toilet and kitchen, FF - Bathroom	Floors	Black cushion vinyl flooring	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	20SM	NA	NA	NA	NA	NA	NA	No action not an ACM	31/03/11			
H				2220AS46 1-006	Roof space	Under roof covering	Sarking felt	Bitumen roofing felts	Discounted material (not sampled)	50SM	NA	NA	NA	NA	NA	NA	No action not an ACM	31/03/11			