

36 Clos Ynysygrug, Trealaw Road, Trealaw, Tonypanydy.					Survey Type >			Management		Initial Survey Date(s) >							20/01/2012						
2220AS556																	Management Action						
Report Section	Extrapolated from Site Ref	UPRN (if applicable)	Lab Ref	Site Ref	Area or room	Position	Component description	Material	Asbestos ID	Extent / approx quantity	** A accessibility	** Damage	** Surface treatment	Asbestos type (1 = Chrysotile, 2 = Amosite, 3 = Crocidolite)	Total Material Risk rating "A"	Total Priority Risk rating "B"	Total Risk Rating "A+B"			Last date ACM inspected	Last date ACM modified	Note	Licensed work?
																		Recommendation					
A			NGA58 74-3	2220AS55 6 -007	External	Under cloak	Lining board	Cement - Fully comp flat sheet, tiles, slates & boards	Positive asbestos sample	2LM	0	0	1	1	3	1	4	Record, manage & monitor	04/12/23				No*
G			NGA58 74-1	2220AS55 6 -003	GF - All areas	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	30SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	20/01/12				
G			NGA58 74-2	2220AS55 6 -004	FF - All areas	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	30SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	20/01/12				
H				2220AS55 6 -001	GF - Kitchen	Under side sink top	Bitumen pad	Bitumen coatings on metal	Discounted material (not sampled)	1No	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	20/01/12				
H				2220AS55 6 -002	GF - Kitchen	Floor	Brown sheet vinyl flooring	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	6SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	20/01/12				
H				2220AS55 6 -005	FF - Bathroom	Floor	Blue sheet vinyl flooring	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	4SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	20/01/12				
H				2220AS55 6 -006	Roof space	Under roof covering	Sarking felt	Bitumen roofing felts	Discounted material (not sampled)	50SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	20/01/12				

* risk assessment required prior to work.

Where 'Carry Out Repairs', 'Seal', 'Encapsulate' or 'Enclose' is recommended, it is implicit that the ACM is also classified as 'Record, Manage and Monitor'.