

11 Oakwood Drive, Thomastown, Porth.				Survey Type >			Management		Initial Survey Date(s) >							08/02/2012							
2220AS587																Management Action							
Report Section	Extrapolated from Site Ref	UPRN (if applicable)	Lab Ref	Site Ref	Area or room	Position	Component description	Material	Asbestos ID	Extent / approx quantity	** Accessibility	** Damage	** Surface treatment	(1 Asbestos type = Chrysotile, 2 = Amosite, 3 = Crocidolite)	Total Material Risk rating "A"	Total Priority Risk rating "B"	Total Risk Rating "A+B"		Last date ACM inspected	Last date ACM modified	Note	Licensed work?	
G			NGA60 08-1	2220AS58 7-003	All areas	Ceilings	'Artex' - 'Stipple'	Textured coatings & joint compound	Negative asbestos sample	44SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	08/02/12				
H				2220AS58 7-001	Kitchen	Under side sink top	Bitumen pad	Bitumen coatings on metal	Discounted material (not sampled)	1No	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	08/02/12				
H				2220AS58 7-002	Kitchen	Floor	Black speck vinyl sheet flooring	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	8SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	08/02/12				
H				2220AS58 7-004	Bathroom	Floor	Tile effect vinyl sheet flooring	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	4SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	08/02/12				
H				2220AS58 7-005	Roof space	Under roof covering	Sarking felt	Bitumen roofing felts	Discounted material (not sampled)	54SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	08/02/12				

\* risk assessment required prior to work.

Where 'Carry Out Repairs', 'Seal', 'Encapsulate' or 'Enclose' is recommended, it is implicit that the ACM is also classified as 'Record, Manage and Monitor'.