

Bathroom - 15 Graig Wen, Maerdy, Ferndale.				Survey Type >		Refurbishment		Initial Survey Date(s) >							06/09/2018								
2220AS719A				Register Type >		Final		Risk ratings							Management Action								
Report Section	Extrapolated from Site Ref	UPRN (if applicable)	Lab Ref	Site Ref	Area or room	Position	Component description	Material	Asbestos ID	Extent / approx quantity	** Accessibility	** Damage	** Surface treatment	Asbestos type (1 = Chrysotile, 2 = Amosite, 3 = Crocidolite)	Total Material Risk rating "A"	Total Priority Risk rating "B" - Score breakdown available on request	Total Risk Rating "A+B"	 Recommendation		Last date ACM inspected	Last date ACM modified	Note	Licensed work?
G			PHH77 83-1	2220AS71 9A-004	Bathroom	Wall under tiles	Adhesive	Textured coatings & joint compound	Negative asbestos sample	2SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	06/09/18				
H				2220AS71 9A-001	Bathroom	Floor	Green sheet vinyl	PVC vinyl floor tiles & unbacked PVC flooring	Discounted material (not sampled)	4SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	06/09/18				
H				2220AS71 9A-002	Bathroom	Bath panel	Lining board	Reinforced plastic and resin composites	Discounted material (not sampled)	2SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	06/09/18				
H			NGAR0 0244-3	2220AS71 9A-003	Bathroom	Ceiling	'Artex' - 'Stipple'	Textured coatings & joint compound	Discounted material (not sampled)	4SM	NA	NA	NA	NA	NA	NA	NA	No action not an ACM	06/09/18			Previously sampled as negative, please refer to 2220AS719-007	

\* risk assessment required prior to work.

Where 'Carry Out Repairs', 'Seal', 'Encapsulate' or 'Enclose' is recommended, it is implicit that the ACM is also classified as 'Record, Manage and Monitor'.